DIMENSIONS IN MILLIMETRES

ITEM	DRAWING No	DESCRIPTION	QTY.	MASS (kg)
1	OEM-MY-7_8x16	7/8" DIA MYLAR INSULATION SLEEVE 16 LONG	8	0.00
2	OEM-100NB-VC	100NB VICTAULIC COUPLING 316 S/S	1	3.7539
3	OEM-100NB-JIS30K-30	100NB JIS30K 3.0mm C-4430 GASKET	1	0
4	11-2933-2	UNIT 11 VALVE 2933-1 DOWN STREAM PIPE 2	1	26.62
5	11-2933-1	UNIT 11 VALVE 2933-1 DOWN STREAM PIPE 1	1	7.28
6		7/8 UNC 2 1/4 HEX BOLT ZP Gr 8	8	0.3
7		7/8" FLAT WASHER G10	8	0.03
8		7/8" FLAT WASHER HIGH TENSILE ZP	8	0.03

RED EYE QR CODE AREA

AS INSTALLED 14/3/25

PIPEWORK MANUFACTURED OF A JIG - FLANGES AS PER DRAWING
DIMENSIONS ARE APPROXIMATE

UNIT 11 VALVE 2933 DOWN STREAM PIPE ASSEMBLY WEIGHT - 40.37 kg

REV	NAME & DATE	DESCRIPTION

UNLESS OTHERWISE SPECIFIED:
TOLERANCES: MACHINE + / - 0.25mm
FABRICATION + / - 1.0 mm

THIS DRG SUPPLIED BY
RODDY ENGINEERING
14 Waratah St, TUMUT NSW 2720
Ph: 02 6947 4039

DRAWING No. 11-2933
REV:

DRAWN N DE BRUYN 27/03/2024
DRAWING CHECKED
DESIGNED
DESIGN CHECKED
SCALE 1:5
WORK ORDER No
APPROVED
SECTION No/KKS
A2 SHEET SIZE

snowyhydro LIMITED

M2 POWER STATION UNIT 11
VALVE 2933 DOWN STREAM PIPE ASSEMBLY

SMA-DRG-NO

REV

SHEET 1 OF 1