ITEM	DRAWING No	DESCRIPTION	QTY.	MASS (kg)
1	OEM-80-PN10-15	80NB EN1092 PN10 1.5mm C-4400 GASKET	2	0
2	OEM-50NB-PN10-15	50NB PN10 1.5mm C-4400 GASKET	6	0
3	3674-60	EMEBEDED PIPE ITEM 2	1	19.32
4	3674-55	EMBEDED PIPE ELBOW ITEM 1	1	16.82
5	3674-50	COOLING WATER PIPE 2	1	50.01
6	3674-45	50NB FLANGE TO 92 SQ SPOOL PIECE WITH SOCKET	3	4.28
7	3674-40	COOLING WATER PIPE 1	1	45.64
8	3674-35	50NB PN16 FLANGE TO 92 SQ SPOOL PIECE	3	3.70
9	3674-30	COOLING WATER PIPE TEE	1	14.46
10		M16x2.0 HEX NUT 304 S/S	40	0.04
11		M16x2.0 x 65 HEX BOLT 304 S/S	40	0.1
12		M16 FLAT WASHER 304 S/S (30x17.5x1.5)	40	0.01

RED EYE QR CODE AREA

VALVES & FLOW METERS FOR ILLUSTRATION ONLY

AS INSTALLED 14/3/25

COOLING WATER HEAT EXCHANGER PIPEWORK WEIGHT - 191.14 kg

PIPEWORK MANUFACTURED OF A JIG - FLANGES AS PER DRAWING
DIMENSIONS ARE APPROXIMATE

REV	NAME & DATE	DESCRIPTION

UNLESS OTHERWISE SPECIFIED:
TOLERANCES: MACHINE + / - 0.25mm
FABRICATION + / - 1.0 mm

THIS DRG SUPPLIED BY
RODDY ENGINEERING
14 Waratah St, TUMUT NSW 2720
Ph: 02 6947 4039

DRAWING No. 3674-25 REV:

DRAWN N DE BRUYN 20/08/2024
DRAWING CHECKED
DESIGNED
DESIGN CHECKED
SCALE 1:20
WORK ORDER No
APPROVED
SECTION No/KKS
A2 SHEET SIZE

snowyhydro LIMITED

M2 POWER STATION UNIT 11
COOLING WATER HEAT EXCHANGER
ASSEMBLIED COOLER PUMP PIPE WORK

SMA-DRG-NO

REV

SHEET 1 OF 1