ITEM	DRAWING No	DESCRIPTION	QTY.	MASS (kg)
1	OEM-80NBx40-T-40-316L	80NB x 40NB BUTT WELD REDUCING TEE 316L S/S	1	2.31
2	OEM-80NB-PN10-SO-316L	80NB PN10 EN1092 SLIP ON FLANGE 316L S/S	2	3.42
3	OEM-40NB-PN10-SO-316L	40NB EN1092-PN10 SLIP ON FLANGE 316L S/S	1	2
4	3674-30-10	80NB & 40NB PIPE SHED 40 316L S/S	1	3.36

AS INSTALLED 14/3/25

PIPEWORK MANUFACTURED OF A JIG - FLANGES AS PER DRAWING
DIMENSIONS ARE APPROXIMATE

COOLING WATER PIPE TEE WEIGHT 74.46 kg

		UNLESS OTHERWISE SPECIFIED: TOLERANCES: MACHINE + / - 0.25mm FABRICATION + / - 1.0 mm	DRAWN N DE BRUYN 17/08/2024	DRAWING CHECKED	snowyhydro LIMITED
		THIS DRG SUPPLIED BY RODDY ENGINEERING 14 Waratah St, TUMUT NSW 2720 Ph: 02 6947 4039	DESIGNED	DESIGN CHECKED	M2 POWER STATION UNIT 11 COOLING WATER HEAT EXCHANGER COOLING WATER PIPE TEE
			SCALE 1:5 WORK ORDER No	APPROVED	
REV	NAME & DATE	DESCRIPTION	DRAWING No. 3674-30 REV:	SECTION No/KKS	A3 SHEET SIZE	SMA-DRG-NO	REV	SHEET 1 OF 1

0,0